

**ITEM 615.1022 08 - ILLUMINATED BOLLARDS**

**DESCRIPTION**

This work shall consist of furnishing and installing ILLUMINATED BOLLARDS in accordance with the contract documents and as directed by the Engineer.

**MATERIALS**

The bollards shall be as specified in the plans unless otherwise approved by the Engineer after consultation with the regional landscape architect. The bollard options and finish shall be as specified in the plans.

**CONSTRUCTION DETAILS**

The contractor shall furnish for approval by the Engineer catalogue cut sheets and any other information requested by the Engineer prior to ordering the material.

The applicable sections of Section 670-3 shall apply.

The bollard shall be installed as recommended by the manufacturer and to the satisfaction of the Engineer.

**METHOD OF MEASUREMENT**

This work will be measured as the number of ILLUMINATED BOLLARDS satisfactorily furnished and installed.

**BASIS OF PAYMENT**

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work. The concrete foundation, conduit and wire shall be paid under their respective items.

DISAPPROVED BY E112-001