

**ITEM 615.1031 08 - BOLLARDS**

**DESCRIPTION**

This work shall consist of furnishing and installing BOLLARDS in accordance with the contract documents and as directed by the Engineer.

**MATERIALS**

The bollards shall be as specified in the plans unless otherwise approved by the Engineer after consultation with the regional landscape architect. The bollard options and finish shall be as specified in the plans.

**CONSTRUCTION DETAILS**

The contractor shall furnish for approval by the Engineer catalogue cut sheets and any other information requested by the Engineer prior to ordering the material.

The bollard shall be installed as recommended by the manufacturer and to the satisfaction of the Engineer.

**METHOD OF MEASUREMENT**

This work will be measured as the number of BOLLARDS satisfactorily furnished and installed.

**BASIS OF PAYMENT**

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work. The foundation shall be paid under its respective item.

DISAPPROVED BY E12-001