

ITEM 615.11 02 M – FABRICATED BOULDERS

DESCRIPTION

The work shall consist of furnishing and installing fabricated boulders in conformance with the details shown on the contract drawings, and where directed by the Engineer.

MATERIALS

Fabricated Boulders. Fabricated boulders shall be of an approved size, shape, color and type as shown in the contract documents and approved by the Engineer in consultation with the Regional Landscape Architect. Fabricated boulder dimensions and weights shall be as shown on the contract drawings.

Fabricated boulders may be obtained from the following supplier:

Rock & Water Creations
815 Fifth Street
Fillmore, CA 93015
(805) 524-5600
<http://www.Rock-n-Water.com>

Rocks Factory.com
Valley Monuments Inc
630 E. Wooley Road
Oxnard, CA 93030
1 (877) 652-1815

Approved Equals from other manufacturers meeting the Item specifications will be considered for acceptance.

Bedding Material. Bedding Material shall be as specified in details on the contract drawings and shall meet the requirements of any Standard Specification Section which applies.

The Contractor shall stockpile the materials at a location approved by the Engineer.

CONSTRUCTION DETAILS

Contractor shall submit cut sheets, product information and installation steps for approval by the Engineer in Charge three weeks prior to delivery.

Fabricated boulders shall be delivered free from any damage or scarring and will be required to be in the same condition after installation.

The Engineer shall be notified three weeks prior to delivery of the fabricated boulders to the construction site. The Contractor shall receive the approval of the Engineer prior to placement of delivered fabricated boulders.

ITEM 615.11 02 M – FABRICATED BOULDERS

The contractor shall notify the Engineer when site preparation is complete. The Engineer, in consultation with the Regional Landscape Architect, will direct the placement of fabricated boulders in the field. Spacing and location of the fabricated boulders shall be as shown on the plans, or as directed by the Engineer. The Contractor shall make adjustments in the fabricated boulders placement as directed by the Engineer. After the arrangement of fabricated boulders is approved by the Engineer, the contractor shall set the fabricated boulders in place and backfill around the fabricated boulders with specified material as shown on the contract drawings, to set the fabricated boulders in a stable position and to prevent future removal or displacement of the fabricated boulders.

METHOD OF MEASUREMENT

Payment for fabricated boulders will be made on a lump sum basis for all work performed in accordance with the plans, specifications and directions of the Engineer for this Item.

BASIS OF PAYMENT

The Lump Sum payment for Fabricated Boulders shall include all labor, material, and equipment and all incidentals and appurtenances necessary to satisfactorily complete the work, including delivery, inspection and installation.

Payment will not be made for repairs to damaged areas caused by the contractors operations. No payment will be made for installing fabricated boulders or work related thereto that has not been accepted by the Engineer or that has degraded due to the Contractors negligence, material failure, or improper storage of the fabricated boulders, bedding material and other materials necessary to complete the installation.

DISAPPROVED BY EIT 12-001