

ITEM 615.1246 08 INDIANA BAT ROOSTING BOX

DESCRIPTION This work shall consist of furnishing and installing Bat Roosting Boxes, posts/poles and metal predator guards as shown in the plans or as directed by the Regional Landscape Architect.

MATERIAL

The Bat Roosting Boxes shall be either The Seven-Chamber Steel Bat House, and or PI or the .25M Bat Can, and or Belfry Sandbox II as manufactured by one of the following, or equals as approved by RLA:

Bat Conservation and Management, Inc.
220 Old Stone House Road,
Carlisle, Pennsylvania 17013

Maberry Centre Bat Homes
1407 Maberry Rd.
Daingerfield, TX 75638

Specification for approved equals should be submitted to RLA three weeks prior to purchase, and will be reviewed and approved by RLA. Confirm approval with EIC or RLA prior to purchase.

Posts/poles and metal predator guards shall be as specified by the manufacturer for the above houses and or the manufacturer of approved equals. Manufacturers' specification, installations instruction shall be made available to the EIC and the RLA three weeks prior to delivery of the Bat Roosting boxes to the project site.

CONSTRUCTION DETAILS

The contractor shall furnish & install all Bat Roosting Boxes, posts/poles and metal predator guards as specified by the manufacturer. Contractor shall locate all boxes as specified in the plans and or as directed by the RLA. RLA will stake all bat roosting box locations on the field prior to installation. The Contractor shall repair any damage that may occur during installation of bat roosting boxes and re-seed and mulch any disturbed soil areas as directed by Regional Landscape Architect.

METHOD OF MEASUREMENT

This work will be measured as the number of acceptable Bat Roosting Boxes, including posts/poles and metal predator guards furnished and installed.

BASIS OF PAYMENT

The unit price shall include the cost of all furnishing labor, materials, and equipment, including any additional seeding and mulching necessary to satisfactorily complete the work.