

## **ITEM 03615.15 M - SWEEPING**

### **DESCRIPTION:**

This work shall consist of sweeping highway shoulders, paved, flush and raised medians and other paved surfaces including gore areas and properly disposing of swept material. The highway travel lanes will not require sweeping.

### **MATERIALS:**

None specified.

### **CONSTRUCTION DETAILS:**

Shoulders, paved medians, paved gutters and other paved surfaces shall be cleaned by the use of mechanical sweepers, hand brooms or other effective means. All sand, vegetation and other debris shall be removed from the shoulders, paved medians and other paved surfaces, except the travel lanes and disposed of as per Subsection 110-08 of the Standard Specifications. Flushing of debris into the highway drainage system shall not be permitted. Dusty conditions resulting from the contractor's operations shall be corrected by the use of water.

### **METHOD OF MEASUREMENT:**

The work will be measured as the number of linear meters of shoulder measured along each edge of roadway along which the above described work is performed. The Engineer will determine the areas where this work is not required.

### **BASIS OF PAYMENT:**

The unit price bid per linear meter for this work shall include the cost of furnishing all labor and equipment necessary to satisfactorily complete the described work and shall include removal and satisfactory disposal of swept material and repair of any damage caused by the Contractor's operations. The cost of water used to control dust shall be included in the unit price bid for sweeping. Hauling and tipping fees are the responsibility of the contractor.