

**ITEM 615.15 08 M – LITTER REMOVAL**

**DESCRIPTION:**

This work shall consist of pick up and removal of debris and litter as shown on the plans, within the limits of this Contract.

**MATERIALS:**

None specified.

**CONSTRUCTION DETAILS:**

The Contractor shall notify the Engineer 48 hours in advance of performing any work under this item. Equipment for litter removal may be selected by the Contractor, but shall be subject to approval of the Engineer. The limits of litter removal are specified in these documents and to the satisfaction of the Engineer. Litter to be removed shall include but not be limited to; metal, plastic, wood, bottles, cans, coffee cups, paper, and food wrappings. The Contractor shall provide receipts for dumping to the Engineer.

**METHOD OF MEASUREMENT:**

The work shall be measured as the number of linear meters along the edge of shoulder or pulloff where the above described work is performed.

**BASIS OF PAYMENT:**

The unit price bid per linear meter for this work shall include the cost of furnishing all labor and equipment necessary to satisfactorily complete the described work and shall include removal and satisfactory disposal of litter and debris plus any repair of damage caused by the Contractor's operations. Hauling and Tipping fees are the responsibility of the Contractor.