

## **ITEM 03615.16 M - LITTER REMOVAL**

### **DESCRIPTION:**

This work shall consist of Pickup and Removal of litter and debris from within the roadside right of way.

### **MATERIALS:**

None specified.

### **CONSTRUCTION DETAILS:**

The contractor shall remove all litter and debris along the project limits from right of way line to right of way line. This area includes all right of way fences, ditches, medians and the area in front of, beneath and behind guide rails. Litter to be removed shall include but not be limited to: tires, metal, plastic, wood, bottles, cans, and paper. Litter shall be disposed of in an approved landfill.

### **METHOD OF MEASUREMENT:**

The work will be measured as the number of linear meters of Right of Way measured along the center of the median along which the above described work is performed. The Engineer will determine the areas where this work is not required.

### **BASIS OF PAYMENT:**

The unit price bid per linear meter for this work shall include the cost of furnishing all labor and equipment necessary to satisfactorily complete the described work and shall include removal and satisfactory disposal of litter and/or debris plus any repair of damage caused by the Contractor's operations. Hauling and Tipping fees are the responsibility of the Contractor