

ITEM 04615.23 M - REMOVE, STOCKPILE AND RELOCATE BOULDERS

DESCRIPTION: Under this item the Contractor shall remove, stockpile and relocate existing onsite boulders where indicated on the plans or where directed by the Engineer.

MATERIALS: Existing boulders shall be used for relocation.

CONSTRUCTION DETAILS:

- a) Removal: The Contractor shall carefully remove and stockpile existing boulders to be relocated. The Contractor shall use caution to minimize any damage to the boulders while moving them.
- b) Stockpiling: The Contractor shall stockpile the boulders in a location approved by the Engineer that will not interfere with the progression of the project and the safety of the traveling public.
- c) Relocation: The Contractor shall reset each boulder as indicated on the plans or as directed by the Engineer.

METHOD OF MEASUREMENT: This work will be measured as the number of boulders relocated in accordance with the plans or as directed by the Engineer.

BASIS OF PAYMENT: The unit price bid for the relocation of each boulder shall include the cost of all labor, materials, tools and machinery necessary to complete the work, including any necessary excavation.

No payment under this item will be made for the removal of boulders which are unusable or otherwise unable to be relocated. Payment for such removal shall be included in the price bid for Clearing and Grubbing.