

**DESCRIPTION**

This work shall consist of relocating, resetting, and reinstalling the play ground equipment in accordance with the contract documents and as directed by the Engineer.

**MATERIALS**

None Specified.

**CONSTRUCTION DETAILS**

The Contractor shall relocate and reinstall play equipment on new surfaces as shown in the contract documents or as directed by the Engineer. All equipment must be installed according to safety regulations that meet or exceed the latest requirements as published in the Handbook for Public Playground Safety - Volumes I and II by the National Bureau of Standards for the U.S. Consumer Product Safety Commission, and ASTM F-1487-01 Standard Consumer Safety Performance Specification for Playground Equipment for Public Use. An independent testing agency must inspect and approve the completed installation. The play ground equipment will not be accepted until the Engineer is satisfied with the installation. No additional compensation will be given for any necessary corrective work.

Any parts damaged or lost by the Contractor's operations shall be replaced by the Contractor at no expense to the State.

The Contractor shall perform the work with all due care, taking precautions to protect the adjacent pavements and structures, and shall be responsible for any damage the Contractor may cause to them during construction.

**METHOD OF MEASUREMENT**

This work will be measured for the payment as the number of existing play structures which have been relocated satisfactorily.

**BASIS OF PAYMENT**

The unit price bid shall include the cost of furnishing all labor, materials, and equipment necessary to satisfactorily complete the work as shown on the contract documents. Concrete footing will be paid separately.