

ITEM 08615.4601 M - DECORATIVE BRICK ENCLOSURE FOR RELOCATED SIGN

DESCRIPTION:

This work shall consist of furnishing and installing a decorative brick enclosure around a relocated commercial sign as shown on the plans and as directed by the Engineer. The contractor shall also remove the existing bluestone cap pieces from the existing brick enclosure and reset them on the new decorative brick enclosure.

MATERIALS:

Brick shall meet the requirements of Section 704-01. The brick color, type and kind of mortar joint shall match the existing brick enclosure.

Mortar shall meet the requirements of Section 705-21.

The existing blue stone cap pieces shall be removed and reset.

CONSTRUCTION DETAILS:

The decorative brick enclosure shall be constructed as shown on the plans or as directed by the Engineer. The contractor shall carefully remove the existing bluestone cap pieces from the existing brick enclosure and reset them on the new brick enclosure. Any damage to these cap pieces caused by the contractor's operation shall be replaced at the contractor's expense.

The existing commercial sign lights shall be connected to the new brick enclosure in a method similar to the existing system.

METHOD OF MEASUREMENT:

This work will be measured as the number of decorative brick enclosures for relocated sign furnished and installed in accordance with plans and specifications.

BASIS OF PAYMENT:

The unit price bid for the decorative brick enclosure for relocated sign including the removal and resetting of the blue stone cap pieces shall include the cost of all labor, materials and equipment necessary to complete the work. The cost of excavation, the concrete foundation, subbase material, sign relocation (including the associated electrical work), and removal of the existing brick enclosure shall be as shown on the plans.