

ITEM 615.8120--04 M - BICYCLE RACK

DESCRIPTION: This work shall consist of furnishing and installing bicycle racks ("Ribbon rack" type in the quantity and at the locations shown on the plans, as listed in the proposal, or as directed by the Engineer.

MATERIALS: Bicycle racks shall be high quality, standard manufactured units that are durable, attractive, structurally sound and vandal resistant. The bicycle rack finish, mounting style and storage capacity shall be as specified on the contract plans. One of the following racks or equal as approved by the Regional Landscape Architect shall be supplied:

CYCLOOPS, Model 2170
Manufacturer: Columbia Cascade
1975 S. W. Fifth Ave., Portland, OR, 97201-5293
(503) 223-1157

or

HEAVY DUTY WINDER, Model HW238
Manufacturer: Madrax
2210 Pinehurst Drive, Middleton, WI, 53562
(800) 448-7931

or

AAA RIBBON BIKE RACK, Model Ribbon
Manufacturer: Brandir International Inc.
521 Fifth Avenue, 17th Floor, New York, NY 10175-1799 USA
800-849-3488

The manufacturer's specifications, installation instructions, and/or brochures in sufficient detail to indicate compliance with this specification shall be made available to the Engineer three weeks prior to delivery of the bicycle rack to the project site.

CONSTRUCTION DETAILS: Racks or parts thereof that are received chipped, scratched, bent, dented or damaged in any way as determined by the Engineer will not be accepted, and shall be removed from the site and replaced with new racks or parts which are free from all defects.

Each bicycle rack shall be permanently installed at its final location in accordance with the manufacturer's recommendation. Racks shall be installed on a concrete base by core drilling four (4) mounting holes and securing the rack with four (4), 13 mm x 150 mm galvanized bolts with matching nuts and washer (Meeting requirements of ASTM A307, Galvanizing).

METHOD OF MEASUREMENT: Bicycle racks will be measured by the number of manufactured units supplied and installed.

ITEM 615.8120--04 M - BICYCLE RACK

BASIS OF PAYMENT: The unit price bid per bicycle rack shall include the cost of all labor, materials, hardware (i.e. bolts washers, nuts flanges, etc.), drilling and grouting for bolts and incidentals necessary to satisfactorily complete the work. Concrete bases shall be paid for under the appropriate item

DISAPPROVED BY EI 12-001