

## **ITEM 08615.9602 M - HELICAL PIER FOR WETLAND BOARDWALK**

### **DESCRIPTION:**

This work shall consist of furnishing and installing the pier system for the wetland boardwalk as shown on the plans or as directed by the Engineer.

### **MATERIALS:**

The pier system for the wetland boardwalk shall be Helical Pier Anchors for Walkway Support or approved equals as manufactured by:

Chance Helical-Pier  
Support System for Walkways  
A.B. Chance Co.  
210 North Allen  
Centralia, MO 65240-1395

All Helical Piles to be Boca approved as per Boca#94-27.

The manufacturer's specifications, installation instructions shall be made available to the Engineer three weeks prior to delivery of the pier system to the project site.

### **CONSTRUCTION DETAILS:**

Pier system parts that are received bent, dented, or damaged in any way as determined by the Engineer will not be accepted, and shall be removed from the project site and replaced. Pier system shall be installed in accordance with the manufacturer's recommendations.

### **METHOD OF MEASUREMENT:**

This work will be measured as the number of manufactured piers supplied and installed in accordance with the plans, specifications or as directed by the Engineer.

### **BASIS OF PAYMENT:**

The unit price bid shall include the cost of furnishing all labor, materials and equipment, including any additional excavation and backfill necessary to complete the work in accordance with the requirements of the contract documents and to the satisfaction of the Engineer.