

**ITEM 619.0210 07 - Work Zone Traffic Control (WZTC) for Bridge Inspection**  
**ITEM 619.0220 07 - Overtime for WZTC for Bridge Inspection**

**Description:**

This work shall consist of providing and furnishing all personnel, including flagpersons where appropriate, and all signs necessary for controlling traffic control when a lane is closed and thru-traffic is to be maintained while using the lightweight Underbridge Inspection Unit (Lwt UBIU), 9 M lift, and/or the 9-27 M lift as directed by the State.

**Materials and Equipment:**

The Contractor, when scheduled by the New York State Department of Transportation, shall supply all necessary personnel and appropriate signs and cones, flashing arrow panels, barrier vehicles and other necessary material to install the proper traffic control as outlined in the National MUTCD and in this proposal.

**Construction Details:**

To control traffic on one or more lanes, the Contractor shall provide adequate traffic controls on the section of highway on which vehicle operation is maintained. The Contractor shall employ a sufficient number of competent flag persons to control traffic continuously. The contractor shall pay attention to Section 107-05, Section A. of the New York State Standard Specifications, the National MUTCD and shall direct traffic in conformance with said manuals.

All provisions contained in the Special Notes section of this Contract shall be adhered to.

**Method of Measurement:**

The method of measurement for this Item is number of days that work zone traffic control is in place, ready for the inspection crew for a contiguous eight hour work duration as described in the General Notes of this Proposal. Note that this eight hour duration varies by Region. Set-up time preceding, and take-down time following, the in-place duration described above shall be included in the per day unit price.

There will be no payment under this Item where lane closure is not warranted or where there is a total closure of a bridge by erecting appropriate signage and traffic is not maintained by the use of flagpersons.

In the event that the bridge inspection personnel require that work zone traffic control be in place outside of the eight hour duration described above, the overtime quantity will be the number of additional hours that the work zone traffic control is in place rounded to the nearest greater half hour.

If delays, interruptions, or terminations of work are experienced, payments may be deducted from the per day bid price in accordance with the Special Notes section of this Contract.

**Basis of Payment:**

**ITEM 619.0210 07 - Work Zone Traffic Control (WZTC) for Bridge Inspection**  
**ITEM 619.0220 07 - Overtime for WZTC for Bridge Inspection**

The unit price bid for this Item shall include the cost for furnishing all labor, flagpersons, overhead, profit, expenses, travel, vehicles, signs and cones, etc. as required to complete the work.

Payment will be made under:

| <i>Item No.</i> | <i>Item</i>  | <i>Pay Unit</i> |
|-----------------|--|-----------------|
| 619.0210 07     | Work Zone Traffic Control<br>For Bridge Inspection | Per Day         |
| 619.0220 07     | Overtime for WZTC For Bridge Inspection            | Per Hour        |