

ITEM 619.0103 63- BASIC WORK ZONE TRAFFIC CONTROL, TRAFFIC LANE CLOSURES FOR INTERSTATE HIGHWAYS, EMERGENCY STANDBY CONTRACT WORK

DESCRIPTION.

This work shall consist of installing, maintaining, and removing lane closures for work sites as defined herein. A standard lane closure is defined as a single or double lane closure for one direction of traffic in accordance with the details provided herewith.

MATERIALS.

All provisions of §619-2.02 shall apply.

CONSTRUCTION DETAILS.

All provisions of §619-3.02 shall apply.

The standard single or double lane closures shall include all the necessary signs, channelizing devices and barrier/shadow vehicles necessary to satisfactorily install the lane closure(s) in accordance with the details herewith.

METHOD OF MEASUREMENT.

Measurement will be made on a calendar day basis. Lane closures less than 4 (four) hours in duration shall be measured as a half (1/2) calendar day.

BASIS OF PAYMENT.

The unit price bid for each calendar day shall include all labor, material and equipment necessary to satisfactory complete this work including daily erection, covering, uncovering, maintaining and removal of signs and devices at work sites.

The unit price for this item will include the maintenance and protection of traffic necessary to install or remove portable traffic signals and temporary concrete barrier.

No daily payment will be made for long term lane closures beyond initial installation and removal.

All flaggers associated with this work will be paid separately under the appropriate item.

Any additional requirements to the standard lane closures (due to variations) shall be paid under their respective items.